


LEGEND

— 100 — TOPOGRAPHIC CONTOUR
INTERVAL = 10 METERS

REF:

TAKEN FROM USGS PENUELAS (1964)
& PUNTA CUCHARA (1964) TOPO QUAD MAPS.



Golder Associates, Inc.
Atlanta, Georgia

CLIENT/PROJECT

BFI OF PONCE, INC.

TITLE

**SITE LOCATION MAP FOR
PONCE MUNICIPAL LANDFILL**

DRAWN

DRC

CHECKED

SDS

REVIEWED

WRS

DATE

6/25/88

SCALE

AS SHOWN

JOB NO.

883-3643

FILE NO.

883-3643

DWG. NO. / REV. NO.


2


FIGURE

1



LOCATION MAP






LEGEND

— APPROXIMATE BOUNDARIES OF LANDFILL

— SITE BOUNDARY

100 TOPOGRAPHIC CONTOUR = 1 METER INTERVALS

NOTE:
BASE MAP PREPARED FROM FEB., 1988 AERIAL PHOTOS.



REVISIONS		
DESCRIPTION	BY	DATE
REVISION 1	DRG	


BFI OF PONCE, INC.

SITE PLAN FOR PONCE MUNICIPAL LANDFILL

DRAWN	DRG	SCALE	AS SHOWN	DATE	6/29/88
CHECKED	EDS	REVIEWED	URS	JOB NO.	883-3643
Golder Associates				DWG NO.	3
				FIGURE	2



LOCATION MAP





0 100 200
SCALE IN METERS
0 400 800
SCALE IN FEET

LEGEND

~ 100~ TOPOGRAPHIC CONTOUR INTERVAL = 10 METERS


REF:
TAKEN FROM RECRA RESEARCH, INC.
RECRA PART B PERMIT APPLICATION.
PENNELAS, P.R. 7 1/2" QUADRANGLE
U.S.G.S. PHOTO REVISED 1982.

CLIENT/PROJECT		 Golder Associates Atlanta, Georgia		TITLE	
BFI OF PONCE, INC.				ORIGINAL SITE TOPOGRAPHY	
DRAWN	CHECKED	REVIEWED	DATE	SCALE	JOB NO.
DRC	ALG	WRS	11/9/88	AS SHOWN	883-3643
FILE NO.			DWG. NO / REV. NO.		FIGURE
883-3643			4		3



-100- TOPOGRAPHIC CONTOUR
INTERVAL = 10 METERS

REF:
TAKEN FROM RECRA RESEARCH, INC.
RCRA PART B PERMIT APPLICATION.



Golder Associates, Inc.
Atlanta, Georgia

CLIENT/PROJECT

BFI OF PONCE, INC.

TITLE

SURFACE WATER/FLOODING MAP

DATE

6/30/88

SCALE

AS SHOWN

JOB NO.

883-3643

DRAWN

DRC

CHECKED

SDS

REVIEWED

WRS

FILE NO.


883-3643

DWG. NO. / REV. NO.

8

FIGURE


4



LEGEND

- CORROGATED STEEL CULVERT
(61cm-24")
DIAMETER
(NOT TO SCALE, LOCATION APPROXIMATE)
- REINFORCED CONCRETE CULVERT
(152cm-60")
DIAMETER
(NOT TO SCALE)
- ARROW INDICATES GENERAL
DIRECTION OF SURFACE WATER RUNOFF
- APPROXIMATE BOUNDARIES OF LANDFILL
- SITE BOUNDARY
- 100 TOPOGRAPHIC CONTOUR: 1 METER
INTERVALS

NOTE: BASE MAP PREPARED FROM FEB., 1988 AERIAL
PHOTOS. DRAINAGE FEATURES PREPARED FROM
BASE MAP.




REFERENCE: JOSE LUIS IRIZARRY AND ASSOCIATES, 1987,
SANITARY LANDFILL, PONCE, PUERTO RICO,
DRAWING NO. C-14; AND
GOLDER ASSOCIATES INC. RECONNAISSANCE
SITE VISIT, 1988.

REVISIONS			BFI OF PONCE, INC.		
DESCRIPTION	BY	DATE	TITLE		
			SITE SURFACE DRAINAGE FEATURES		
			DRAWN	EAH	SCALE AS SHOWN
			CHECKED	ALG	REVIEWED WRS
			DATE	12/21/88	JOB NO. 883-3643
			DWG NO.	36	FIGURE 5
			Golder Associates		


PUERTO RICO

PONCE SITE

LOCATION MAP



REF: FROM RECRA RESEARCH, INC.
RECRA PART B PERMIT APPLICATION (1984)
AND GOLDER ASSOCIATES, INC. SITE
RECONNAISSANCE, NOV., 1988.



Golder Associates Inc.
Atlanta, Georgia

CLIENT/PROJECT

BFI OF PONCE, INC.


TITLE

SURROUNDING LAND USE MAP

DATE	11/10/88	SCALE	AS SHOWN	JOB NO.	883-3643
FILE NO.	883-3643	DWG. NO. / REV. NO.		FIGURE	6

DRAWN	DRC	CHECKED	ALG	REVIEWED	WRS
-------	-----	---------	-----	----------	-----

CALM- 5.1%



LOCATION:
PONCE, PUERTO RICO (STATION #11637)
SOURCE:
U.S. DEPT. OF COMMERCE, NATIONAL OCEANIC
AND ATMOSPHERIC ADMINISTRATION
PERIOD: MARCH, 1951 THROUGH MARCH, 1954
NUMBER OF OBSERVATIONS:27,012



Golder Associates
Atlanta, Georgia

CLIENT/PROJECT

BFI OF PONCE, INC.

TITLE

WIND ROSE OF PONCE, PR.

DATE **11/9/88**

SCALE **AS SHOWN**

JOB NO. **883-3643**

DRAWN **DRC**


CHECKED **ALG**

REVIEWED **WRS**

FILE NO. **883-3643**

DWG. NO. / REV. NO.

FIGURE **7**



CLIENT/PROJECT

BFI OF PONCE, INC.



Golder Associates, Inc.

Atlanta, Georgia

TITLE

**LOCATION MAP FOR PONCE
MUNICIPAL WELLS**

DRAWN

DRC

CHECKED

SDS

REVIEWED

WRS

DATE

7/8/88

SCALE

AS SHOWN

JOB NO.

883-3643

FILE NO.

883-3643

DWG. NO. / REV. NO.


25


FIGURE

8




LOCATION MAP



CLIENT/PROJECT		 Golder Associates Atlanta, Georgia			TITLE		
BFI OF PONCE, INC.					ABANDONED WATER WELLS		
DRAWN	DRC	CHECKED	ALG	REVIEWED	WRS	DATE	11/8/88
		SCALE		AS SHOWN		JOB NO.	
				883-3643		FILE NO.	
				883-3643		DWG. NO / REV. NO.	
						FIGURE	
						9	

CORRELATION OF MAP UNITS



CONTACT-DOTTED WHERE CONCEALED; QUERIED WHERE INFERRED (CONTACTS OF QUATERNARY ALLUVIAL UNITS ARE SHOWN BY A SOLID LINE BY CONVENTION; PLACEMENT RANGES FROM ASSURED TO INFERRED).

FAULT- LONG DASHED WHERE APPROXIMATELY LOCATED; SHORT DASHED WHERE INFERRED; DOTTED WHERE CONCEALED; BALL AND BAR ON DOWNTOWN SIDE; WRENCH FAULT AND RELATIVE DIRECTIONS OF MOVEMENT SHOWN BY ARROWS; A, AWAY FROM OBSERVER; B, TOWARDS OBSERVER.

FOLDS- SHOWING CRESTLINE OR TROUGHLINE, DIRECTION AND AMOUNT OF PLUNGE IF KNOWN AND DIRECTION OF DIP OF LIMBS, LONG DASHED WHERE APPROXIMATELY LOCATED, DOTTED WHERE CONCEALED.

ANTICLINE

SYNCLINE

10 STRIKE AND DIP OF BEDS INCLINED

INCLINED CONSPICUOUS BEDS OF Kgpbl OR Kgps IN Ky.

Golder Associates, Inc.
Atlanta, Georgia

AGENT/PROJECT

BFI OF PONCE, INC.

AWN

DRC

CHECKED

SDS

REVIEWED

WRS

TITLE

REGIONAL GEOLOGIC MAP

DATE

6/29/88

SCALE

AS SHOWN

JOB NO.

883-3643

FILE NO.


883-3643

DWG. NO. / REV. NO.


5

FIGURE

10




REF:
TAKEN FROM USGS PENUELAS (1964) &
PUNTA CUCHARA (1964) TOPO QUAD MAPS.
CONTOURS ARE 10m INTERVALS





C-16



LEGEND

--- SITE BOUNDARY


100 TOPOGRAPHIC CONTOUR
INTERVAL = 5 METERS

C-2
● OBSERVATION WELL
(LAW ENGINEERING
TESTING CO., 1983a)

MW-3
⊕ MONITORING WELL
(LAW ENGINEERING
TESTING CO., 1983c &
1984d).

U
D FAULT (U, UPTHROWN SIDE,
D, DOWNTOWN SIDE).

REF:
TAKEN FROM RECRA RESEARCH, INC.
RCRA PART B PERMIT APPLICATION.



Golder Associates, Inc.
Atlanta, Georgia

CLIENT/PROJECT

BFI OF PONCE, INC.

DRAWN

DRC

CHECKED

SDS

REVIEWED

WRS

TITLE

**OBSERVATION AND MONITORING
WELLS**

DATE

7/8/88

SCALE

AS SHOWN

JOB NO.

883-3643

FILE NO.

883-3643

DWG. NO. / REV. NO.

15

FIGURE

13



Golder Associates Inc.

CONSULTING ENGINEERS

RECEIVED
AGENCY REPORT
1989 JUN 21 PM 4:06
PERMITS BRANCH

POST-CLOSURE PERMIT APPLICATION

VOLUME II OF IV

Submitted to:

BFI of Ponce, Inc.
757 North Eldridge
Houston, Texas 77079

DISTRIBUTION:

- 2 Copies - BFI, Houston, Texas
- 4 Copies - U.S. EPA, Region II
- 1 Copy - Environmental Quality Board, Puerto Rico
- 1 Copy - BFI of Ponce, Puerto Rico
- 2 Copies - Golder Associates Inc.

Revision 1
May 1989

883-3643

TABLE OF CONTENTS

VOLUME I OF IV

Cover Letter

Executive Summary i

Table of Contents v

SECTION PAGE

A. PART A APPLICATION

B. FACILITY DESCRIPTION..... 1

B.1 General Description (40 CFR 270.14(b)(1))..... 1

B.1.1 Description of Facility..... 2

B.2 Topographic Map (40 CFR 270.14(b)(19))..... 3

B.2.1 General..... 3

B.2.2 One Hundred Year Floodplain Area..... 3

B.2.3 Surface Waters..... 3

B.2.4 Surrounding Land Use..... 4

B.2.5 Wind Rose..... 4

B.2.6 Legal Boundary..... 4

B.2.7 Location of Access Control..... 5

B.2.8 Locations of Injection and Withdrawal
Wells..... 5

B.2.9 Locations of Buildings and Structures.. 5

B.2.10 Location of Sanitary Sewers..... 6

B.3 Additional Requirements for Land Facilities
(40 CFR 270.14(c)(3) and (4)(i), 264.95,
264.97)..... 6

B.4 Seismic Compliance (40 CFR 270.14(b)(11)(i)).. 7

B.5 Floodplain Standard (40 CFR 270.14(b)(11)(iii),
264.18(b))..... 13

C. WASTE CHARACTERISTICS (40 CFR 270.14(b)(2),
264.13(a))..... 14

D. PROCESS INFORMATION (40 CFR 270.219(a))..... 19

D.1 Current Landfill Practices..... 19

E. GROUNDWATER MONITORING..... 23

E.1 Interim Status Monitoring (40 CFR 270.14(c)(1),
265.90-265.94)..... 23

E.2 Aquifer Identification (40 CFR 270.14(c)(2)).. 23

E.3 Contaminant Plume Description (40 CFR 270.14
(c)(4), Part 261, Appendix VIII)..... 19

E.4 Detection Monitoring Program (40 CFR 270.14
(c)(6), 264.98) 24

E.4.1 General 24

E.4.2 Selection of Parameters..... 25

E.4.3 Elements of the Monitoring Program..... 26

E.5 Schedule..... 27

F.	PROCEDURES TO PREVENT HAZARDS.....	28
G.	CONTINGENCY PLAN (40 CFR 270.149(b)(7), 264.50 through 264.56, 264.52(b)).....	30
H.	PERSONNEL TRAINING (40 CFR 270.14(b)(12), 264.16)..	31
I.	CLOSURE AND POST-CLOSURE REQUIREMENTS (40 CFR 270.14(b)(13), 264.110 through 264.120)....	32
I.1	Closure Plan (40 CFR 270.14 (b)(13), 264.112(a)(1) and (2)).....	32
I.1.1	General.....	32
I.1.2	Closure Performance Standard.....	33
I.1.3	Maximum Waste Inventory.....	33
I.1.4	Detailed Schedule for Closure.....	34
I.1.5	Certification of Completion of Closure	34
I.1.6	Survey Plat.....	34
I.2	Post-Closure Plan (40 CFR 270.14(b)(13), 270.21(e), 264.118, 264.310(b)).....	35
I.2.1	General.....	35
I.2.2	Inspection and Maintenance Plan.....	35
I.2.3	Monitoring Plan.....	37
I.2.4	Post-Closure Security.....	38
I.2.5	Contact.....	38
I.2.6	Post-Closure Certification.....	38
I.3	Post-Closure Notices (40 CFR 270.14(b)(14), 264.119).....	39
I.3.1	Notice to Local Zoning Authority.....	39
I.3.2	Notice in Deed to Property.....	39
I.4	Closure Cost Estimate (40 CFR 270.14(b)(15), 264.142).....	39
I.5	Financial Assurance Mechanism for Closure (40 CFR 270.14(b)(15), 264.143).....	40
I.6	Post-Closure Cost Estimate (40 CFR 270.14(b) (16), 264.144).....	40
I.7	Financial Assurance Mechanism for Post-Closure Care (40 CFR 270.14(b)(16), 264.145).....	41
I.8	Liability Requirements (40 CFR 270.14(b)(17), 264.147)	41
J.	CORRECTIVE ACTION FOR SOLID WASTE MANAGEMENT UNITS.....	42
K.	OTHER FEDERAL LAWS (40 CFR 270.3 AND 270.14(b)(20)).....	43
K.1	The Wildlife and Scenic Rivers Act [16 USC 1273 et. seq.]	43
K.2	The National Historic Preservation Act of 1966 [16 USC 470 et. seq., 36 CFR 800].....	43
K.3	The Endangered Species Act [16 USC 1531 et. seq., 50 CFR 402].....	44
K.4	The Coastal Zone Management Act [16 USC 1451 et. seq., 15 CFR 930]	44

K.5	The Fish and Wildlife Coordination Act [16 USC 661 et. seq.]	45
L.	PART B CERTIFICATION.....	46
	REFERENCES.....	47

In Order
Following
Page 47

TABLE 1 - Summary of References on Elements of the Monitoring Plan

TABLE 2 - Compliance Schedule

FIGURE 1	- Site Location Map for Ponce Municipal Landfill
FIGURE 2	- Site Plan for Ponce Municipal Landfill
FIGURE 3	- Original Site Topography
FIGURE 4	- Surface Water/Flooding Map
FIGURE 5	- Site Surface Drainage Features
FIGURE 6	- Surrounding Land Use Map
FIGURE 7	- Wind Rose of Ponce, PR
FIGURE 8	- Location Map for Ponce Municipal Wells
FIGURE 9	- Abandoned Water Wells
FIGURE 10	- Regional Geologic Map
FIGURE 11	- Site Geologic Map
FIGURE 12	- Flood Insurance Rate Map
FIGURE 13	- Observation and Monitoring Wells

VOLUME II OF IV

ATTACHMENT 1	- RCRA Facility Assessment, Landfill Operational Practice
ATTACHMENT 2	- RFA Work Plan, Cover Soil Sampling
ATTACHMENT 3	- RFA Work Plan, Sampling of Soil Beneath Landfill
ATTACHMENT 4	- Hydrogeologic Review

VOLUME III OF IV

ATTACHMENT 5	- Groundwater Monitoring Plan
ATTACHMENT 6	- Quality Assurance Plan for Laboratory Analysis and Field Instrument Maintenance

VOLUME IV OF IV

ATTACHMENT 7	- Report on Fault Age
ATTACHMENT 8	- Solidification Procedures
ATTACHMENT 9	- BFI's Requirements for Chemical/Industrial Waste Disposal Approval
ATTACHMENT 10	- Analytical Results and Field Report for Groundwater Sampling
ATTACHMENT 11	- Investigation of Near-Surface Moisture Movement in Juana Diaz Formation

Revision 1
May 1989

-viii-

883-3643

ATTACHMENT 12 - BFIP's Operation Plan
ATTACHMENT 13 - Training for Landfill Personnel
ATTACHMENT 14 - Landfill Volume Calculations
ATTACHMENT 15 - Certificate of Insurance

ATTACHMENT 1

RCRA FACILITY ASSESSMENT
LANDFILL OPERATIONAL PRACTICE
PONCE MUNICIPAL LANDFILL
PONCE, PUERTO RICO

July 1988

883-3643



Golder Associates Inc.
CONSULTING ENGINEERS

July 22, 1988

883-3643

Browning-Ferris Industries
of Ponce, Inc.
P.O. Box 3151
Houston, Texas 77254

Attention: Mr. Bruce Jernigan
Divisional Vice President

RE: REPORT ON LANDFILL OPERATIONAL PRACTICES
PONCE MUNICIPAL LANDFILL
PONCE, PUERTO RICO

Gentlemen:

We are pleased to submit the following report on Landfill
Operational Practices for the Ponce Municipal Landfill.

We appreciate the opportunity to assist BFI on this project.

Very truly yours,

GOLDER ASSOCIATES, INC.

W. Randall Sullivan, P.E.
Associate

WRS/r

TABLE OF CONTENTS

Cover Letter

Table of Contents

i

<u>SECTION</u>	<u>PAGE</u>
1.0 INTRODUCTION.....	1
2.0 SITE DESCRIPTION.....	3
2.1 Site Location.....	3
2.2 Site History.....	3
2.3 Topography.....	4
2.4 Geology.....	5
2.5 Climate.....	6
3.0 OPERATIONS.....	8
3.1 Site Facilities.....	8
3.2 Nature of Wastes.....	8
3.2.1 Current Practice.....	8
3.2.2 Previous Practice.....	9
3.3 Equipment.....	10
3.4 Method of Placing Refuse.....	11
3.5 Cover.....	12
3.6 Leachate Management.....	13
4.0 SURFACE HYDROLOGY.....	14
4.1 Hydrology.....	14
4.2 Surface Runoff Control.....	14
5.0 INVESTIGATIONS OF LANDFILL AND WASTE.....	16
5.1 General.....	16
5.2 Landfill.....	16
5.3 Soil Beneath Landfill.....	19
6.0 SLOPE STABILITY.....	20
6.1 Stability of Natural and Cut Slopes.....	20
6.2 Stability of Landfill.....	21
REFERENCES.....	23

TABLE OF CONTENTS

TABLE 1 - Summary of Boring Data	In Order
TABLE 2 - Summary of Analytical Results for Landfill Composites	Following
TABLE 3 - Summary of Analytical Results for the Roadway Sidewall Composites	Page 23
FIGURE 1 - Site Location Map for Ponce Municipal Landfill	
FIGURE 2 - Site Plan for Ponce Municipal Landfill	
FIGURE 3 - Original Site Topography	
FIGURE 4 - Site Geologic Map	
FIGURE 5 - Annual Precipitation	
FIGURE 6 - Average Annual Temperatures in Puerto Rico	
FIGURE 7 - Surface Water/Flooding Map	
FIGURE 8 - Boring Locations CA-1 to CA-8	
FIGURE 9 - Placement of Waste in Cells	
FIGURE 10 - Isopachs of Landfill Thickness	
FIGURE 11 - Isopleths of Elevation of Base of Landfill	

1.0 INTRODUCTION

This report describes operational practice at the Ponce Municipal Landfill which is operated by Browning-Ferris Industries of Ponce, Inc. (BFIP). The report has been prepared by Golder Associates, Inc. under authorization from BFIP.

This report is one of six documents requested by BFIP which form the basis of a RCRA Facility Assessment. Brief titles of the six documents are:

- (i) Landfill Operational Practice
- (ii) Plan for Cover Soil Sampling
- (iii) Plan for Sampling of Soil Beneath Landfill
- (iv) RFA Schedule
- (v) Hydrogeologic Review
- (vi) Groundwater Monitoring Plan

This report provides an outline of current operational practice and forms a basis for site characterization. The report includes:

- o a description of the site location, history, topography, geology and climate;
- o operational practice, including site facilities, the nature of the refuse, the method of placing refuse, a description of cover material used and the method of placing cover;
- o surface hydrology of the site including leachate management and surface water runoff control;
- o a summary of previous investigations performed in the landfill which provide characterization of the refuse; and

- o an assessment of slope stability at the site including stability of natural and cut slopes and the stability of the landfill itself.

The review is based on information supplied by BFIP, discussions with BFIP personnel and reports of previous studies at the site prepared by a variety of consultants.

Previous studies referenced in this document were prepared by the following organizations:

- o Cecos International, Inc.
- o Recra Research, Inc.
- o Law Engineering Testing Company
- o M.T. Davisson, Consulting Engineer
- o BFI of Ponce, Inc.

Most of the documents are included in the RCRA Part B Permit Application for a Hazardous Waste Management Facility proposed for the site. Some additional information has been obtained from BFIP documents for the site. A list of references is included at the conclusion of this report.

2.0 SITE DESCRIPTION

2.1 Site Location

The Ponce Landfill Site is located on Avenue Baramaya, Barrio La Cotorra in the south-central portion of Puerto Rico, 1 to 2 km outside the city limits of Ponce and 3 km north of the Caribbean Sea (Figure 1). The site covers an area of 51 ha (125 acres) with approximately two-thirds of the area being covered by fill or subjected to borrow excavation.

The layout of the site is shown on Figure 2, Site Plan. The approximate limits of the landfill are designated on the Site Plan, indicating filling of a valley. Site workshops, offices and other facilities are located at the eastern end of the site. An unused waste cell (Cell 1), excavated during 1983-84 is located on the south side of the site. Current borrow areas for cover material are located to the northeast and southwest of the landfill.

2.2 Site History

Site history was documented in the RCRA Part B Application by Law Engineering (1983a). Examination of aerial photographs indicated that the site was uninhabited and used as grazing land until sometime between 1936 and 1951. During that period grazing was discontinued and thick brush redeveloped.

By 1967 quarrying had taken place along the northern and southern sides of the ridge occupying the southwestern portion of the site. Some waste disposal had occurred on the site, primarily within the north-central valley.

By 1971 quarrying operations had extended to the hills on the east side of the site (in the Ponce Formation). Further random waste disposal appeared to have been taking place. By

1977 the site was being used much as it is at present with landfilling occurring throughout the central portion of the valley and cover material being borrowed from the surrounding hills. Examination of photographs from 1977 indicates that two waste lagoons were being constructed on the western edge of the site.

An oblique aerial photograph from 1983 indicates that the unused Cell 1 was under construction. Two waste lagoons, formerly operated by SK & F Industries, were evident on the western edge of the site. Closure of these lagoons was completed by September 24, 1983 in accordance with closure plans submitted to and approved by USEPA Region II.

The Ponce Municipal Landfill has been operated for disposal of municipal refuse since June 1, 1983 by Cecos International, Inc., a subsidiary of Browning-Ferris Industries, and solely by BFIP since March 1, 1987, under an agreement with the City of Ponce.

2.3 Topography

The local site topography is characterized by rugged hills in a semi-arid environment. Much of the site topography has been altered by quarrying and subsequent filling of the on-site drainage features with waste and filling. The hill in the southwest corner alone remains unchanged.

Site topographic elevations range between 40 m and 140 m (130 and 450 feet) above mean sea level (MSL). The highest part of the landfill is at an elevation of 100 m (328 feet) MSL.

Topography prior to filling is shown on Figure 3, and is based on data obtained in 1941 and 1943. This figure indicates a creek flowing from the north towards the middle of the site where it swings eastward, crossing the property boundary near the current entrance to the site.

Major drainage features in the area are the Rio Pastillo to the east and the Quebrada del Agua to the west. Both of these rivers drain southward to the Caribbean Sea. These rivers do not flow for about 70 percent of the year.

2.4 Geology

The Ponce site is located within the Southern Carbonate Province of Puerto Rico. This province is a narrow band, roughly 8 km (5 miles) wide, and extends about 50 km (30 miles) east and west of Ponce. Overlying the Cretaceous rocks of the Central Cordillera, thick carbonate sequences were deposited in this province during the mid-Tertiary age. These thick carbonate deposits were exposed by the uplift movements which began in the Pliocene and continued perhaps into the Quarternary. Quarternary alluvial deposits cover a localized area of the southern portion of the carbonate sequences.

Two formations are recognized within the south Puerto Rico Carbonate Province and both are present at the site as indicated on the Site Geologic Map (Figure 4). The Juana Diaz Formation is of mid-Oligocene to Miocene age and consists of white to brown and greyish-orange bedded calcareous arenites and siltstones with variable clay content.

The Ponce Formation is orange, very fossiliferous and porous except near the base where a hard crystalline member and a

homogenous silty member overlies the Juana Diaz beds in slight unconformity

A fault crosses the site in an east-west direction and displaces Juana Diaz beds to the south against mid-Ponce limestone to the north. It is a high-angle normal fault with at least 200 m (650 feet) of vertical displacement and possibly a left-lateral component of offset. The inferred location of this fault is shown on Figure 4. Smaller faults mapped within the Juana Diaz Formation are also shown on Figure 4.

The east-west fault divides the site into the northern half which is underlain by Ponce Formation and the southern half which is underlain predominantly by Juana Diaz Formation. However, detailed mapping of the site has revealed that the southern hills are capped by the lower Ponce beds which unconformably overlies the Juana Diaz Formation.

2.5 Climate

The climatic setting of the Ponce Landfill Site is discussed in some detail in the RCRA Part B Permit Application. The following discussion summarizes the significant climatic features of the Ponce area.

Ponce is located in the southern coastal climatological province of Puerto Rico. The dominant winds in the area are the trade winds which are principally from the northeast and southeast. About 60% of the winds have a velocity between 9 and 26 km/hr (4 and 12 mph) with an average of 11 km/hr (5 mph). The winds primarily account for the high continuous rate of evaporation at Ponce.

The rainfall precipitation patterns and quantities, as well as evaporation rates, are significantly different on the south side of the island at Ponce compared to those on the northern side of the island near San Juan.

Annual rainfall, analyzed for the years 1955-1981, yield long term precipitation on an annual basis as follows:

<u>Years</u>	<u>Average Annual Rainfall</u>
1955-1976	815 mm (32.07 inches)
1977-1981	826 mm (32.50 inches)
1955-1981	817 mm (32.15 inches)

The annual rainfall amount changes significantly from year to year (Figure 5) for the ten year period of 1972-1981. The hurricane season runs from June to mid-October and may produce up to 1000 mm (40 inches) of rain per event. Peak rainfall months for Ponce are generally from May to September.

Pan evaporation data obtained for the years 1983-1987 indicate relatively high rates, averaging nearly 1200 mm (47 inches) per year.